BRUHAT BENGALURU MAHANAGARA PALIKE

Tender Notification No. EE/SWD/YZ/TEND/02/2013-14, DATED: 21-10-2014

DRAFT TENDER SCHEDULE

Name of the Work: Remodeling of SWD BP 026 (BY03) from BB Nagara, Kodigehalli to H-200 primary drain near Nagashettihalli main road in ward no.08, in Yelahanka Zone

Sl. No	Item Code	Description	Unit	Quantity	SR Rate in Figure	Rate in Figures	Rate in Words
1	1	Diversion of water course by providing Coffer dams or bunds or islands as may be necessary for piers and abutments foundations, bailing out or pumping water during excavation and until completion etc., complte. 1.50 mtrs depth below LWL with all lead and lifts as directed by the Engineer-in-charge.	Cum	462.44	330.48		
2	2	KSRRB M2100-5.1: Earth work in excavation for foundation of structures as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material complete as per specifications. "V. Marshy soil - A.Manual Means upto 3 m depth . MORTH Specification No.304 with all lead and lifts as directed by the Engineer-in-charge.	Cum	353.34	116.64		
3	3	KSRRB M200-12.3 Dismantling of Existing Structures like Culverts,Bridges,Retaining Walls and other structures comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding where ever necessary,sorting the dismantled material,disposal of unserviceable material and stacking the seviceable material with all lifts complete as per specifications.(Prestressed/ reinforced cement concrete grade M20 and above) with all lead and lifts as directed by the Engineer-in-charge.	Cum	33.30	954.72		

Sl. No	Item Code	Description	Unit	Quantity	SR Rate in Figure	Rate in Figures	Rate in Words
4	4	KSRRB M200-15.2 : Dismantling of existing structures like culverts, bridges retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work including T & P and scaffolding wherever necessary sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres complete as per specification.iii) Dismantling Stone Masonry. B.Rubble Stone masonry in cement mortar with all lead and lifts as directed by the Engineer-in-charge.	Cum	271.80	226.80		
5	5	KSRRB M200-12.2: Dismantling of existing structures like culverts, bridges retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work including T & P and scaffolding wherever necessary sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres complete as per specification. i) Lime/Cement concrete. I.By Manual means : A. Lime/Cement Concrete, I.By Manual means : B cement concrete Grade M-15 & M-20 with all lead and lifts as directed by the Engineer-in-charge.	Cum	120.80	347.76		
6	6	KSRRB M2100-2.1 : Earth work in excavation for foundation of structures as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material complete as per specifications. B. Mechanical Means (i) Depth upto 3 m. MORTH Specification No.Section 304. In ordinary soil with all lead and lifts as directed by the Engineer-in-charge.	Cum	2028.70	43.20		

Sl. No	Item Code	Description	Unit	Quantity	SR Rate in Figure	Rate in Figures	Rate in Words
7	7	KSRB 2.8 : Providing and Filling in foundation with granite/trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead upto 50m and lift of 1.5m complete as per specifications.Specification No.KBS with all lead and lifts as directed by the Engineer-in-charge.	Cum	226.50	1962.36		
8	8	KSRRB M2100-10 : Plain cement concrete M 10 with OPC cement @ 220 kgs with crushed 40m and down size graded grantie metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications. MORTH Specification No.2100 with all lead and lifts as directed by the Engineer-in-charge.	Cum	113.25	5171.04		
9	9	KSRRB M2700-6 : PCC M15 Grade leveling course below approach slab complete as per drawings and technical specifications complete as per specifications. MORTH specification No.2700 with all lead and lifts as directed by the Engineer-in-charge.	Cum	44.55	5328.72		
10	10	KSRRB M2100-20.2 : Plain / Reinforced Cement concrete in open foundation with OPC cement design mix M35 @ 390 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.68 cum and fine aggregates @ 0.45 cum with superplastisiser @ 3lts confirming to IS 9103-1999 Reaffirmed-2010complete as per drawing and technical specification. Case-II : With Batching Plant, Transit Mixer and Concrete Pump. MORTH Specification No.1500, 1700 & 2100 with all lead and lifts as directed by the Engineer-in-charge.	Cum	376.75	6008.04		

Sl. No	Item Code	Description	Unit	Quantity	SR Rate in Figure	Rate in Figures	Rate in Words
11	11	KSRRB M2200-5.18 : Design mix M 35 with OPC cement @ 390kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.68cum and fine aggregates @ 0.45 cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008 i) upto 5m height with all lead and lifts as directed by the Engineer-in-charge.	Cum	226.24	6728.40		
12	12	KSRRB M2300-8.1 : Furnishing and Placing Reinforced / Prestressed cement concrete in super-structure as per drawing and Technical Specification complete as. per specifications. D.RCC/PSC with OPC cement design mix M35 @ 390kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.68cum and fine aggregates @ 0.45cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008. Case-II : Using Batching plant, Transit mixer & concrete pump Height upto 5m with all lead and lifts as directed by the Engineer-in-charge.	Cum	306.93	6847.20		
13	13	KSRRB M2200-6: Supplying, fitting and placing TMT bar reinforcement in sub-structure as per drawing and Technical Specifications complete as per specifications. MORTH Specification No.1600 & 2200 with all lead and lifts as directed by the Engineer-in-charge.	MT	64.07	72390.24		
14	14	KSRRB M2300-14 : Supplying, fitting and placing TMT bar reinforcement in super-structure complete as per drawing and technical specifications complete as per specifications. MORTH specification No.1600 with all lead and lifts as directed by the Engineer-in-charge.	MT	33.76	73193.76		
15	15	Providing 90mm dia PVC pipes 10 KSC for weep holes as directed by the Engineer in charge.	Rmt	120.80	350.00		

Sl. No	Item Code	Description	Unit	Quantity	SR Rate in Figure	Rate in Figures	Rate in Words
16	16	KSRRB M2700-7 : Reinforced cement concrete M30 approach slab including reinforcement and form work complete as per drawings and technical specifications complete as per specifications.MORTH specification No.1500, 1600, 1700, & 2704 with all lead and lifts as directed by the Engineer-in-charge.	Cum	89.10	10648.80		
17	17	KSRRB M2600-4 : (iii) Providing and fixing in position 20mm thick premoulded joint filler in expansion joint for fixed ends of simply supported spans not exceeding 10m to cater for a horizontal movement upto 20mm covered with sealant complete as per drawing & Technical specification complete as per specifications. MORTH specification No.2605 with all lead and lifts as directed by the Engineer-in-charge.	Rmt	13.50	174.96		
18	18	KSRRB 300-49 : Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by manual means without disturbing the base and stacking of the debris materials within a lead of 100 mtrs including cost of all labour charges complete as per specifications. MORTH / Chapter 3 with all lead and lifts as directed by the Engineer-in-charge.	Sqm	297.00	52.92		
19	19	KSRRB 300-45 : Scarifying stone metal crust 50mm to 100mm thick with pick axes along with premix carpet / surface dressing and stackign of old serviceable materials within a lead of 100 metres by manual means including cost of all labour charges complete as per specifications. MORTH / Chapter 3 with all lead and lifts as directed by the Engineer-in-charge.	Sqm	297.00	46.44		

Sl. No	Item Code	Description	Unit	Quantity	SR Rate in Figure	Rate in Figures	Rate in Words
20	20	KSRRB M400.14.1 : Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel / vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding materials to fill up the interstices of coarse agreegate, watering and compacting to the required density complete as per specification.A by Manual means. Type A 13.2mm for grading II. MORTH Specification No.404 with all lead and lifts as directed by the Engineer-in-charge.	Cum	44.55	1672.92		
21	21	KSRRB M400.14.1 : Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel / vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding materials to fill up the interstices of coarse agreegate, watering and compacting to the required density complete as per specification.A by Manual means. Type B 11.2mm for grading III. MORTH Specification No.404 with all lead and lifts as directed by the Engineer-in-charge.	Cum	29.70	1798.20		
22	22	Collecting, conveying and disposal of surplus / excavated earth to designated dupmping site (15.00 kms) as directed by the Engineer in charge.	Cum	1014.35	109.51		

Actual amount of work portion Rs 1,59,42,964-00 only.

No of Corrections = 1

" DTS Approved "

ಮುಖ್ಯ ಅಭಿಯಂತರರು/ಇ.
ಬೃಹತ್ ಮಳೆ ನೀರಿನ ಚರಂಡಿ,
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃ.ನೀ.ಗಾ., ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ